



ODISHA COMPUTER APPLICATION CENTRE
OCAC BUILDING, N-1/7-D,
ACHARYA VIHAR SQUARE, NEXT TO PLANETORIUM,
BHUBANESWAR - 751013

Our Ref: No. OCAC-CAD -08/2021/- 4773 / Dated 09/11/23

SHORT QUOTATION CALL NOTICE

Sealed quotations are invited from authorized supplier/dealer/contractor having valid document as mentioned below for "Providing repair maintenance of washroom of 5th floor with complete flooring & water proofing works including replacement of damaged pipe line & accessories with other miscellaneous works at OCAC Tower", Bhubaneswar.

Sl No.	Description of Work	Qty	Unit	RateRs.	Amount
1	Cleaning and removal of debris by Trailer within 5 km lead including loading and unloading with Hydraulic Excavator 1cum bucket capacity from outside the OCAC premises etc. complete as per the direction of Engineer-in-Charge.	5.00	Trip		
2	Providing , Fitting & Fixing Ceramic Floor Tiles in flooring using special plain / printed series Ceramic Floor Tile of premium grade (having minimum thickness 7 mm.to 8 mm. & size 300 m.m x 300 m.m OR 400 m.m x400 m.m) confirming to I.S 13755 of approved quality and shade in floors, treads on steps and landings in all floors at all height on 25 m.m thick bed of cement mortar of mix (1:1) laid in proper slope and gradient with screened and washed sharp river sand for mortar and grouted with neat white cement slurry, joining the Ceramic Floor Tiles with neat white cement slurry, mixed with required quantities of pigments of approved marks to match the shades of the Ceramic Floor Tiles if required (Tiles are to be immersed in the water for required time before use) including cost, conveyance, loading, unloading, stacking, royalties and taxes of all Materials, cost of all Labor, Sundries, required for the work , watering and curing for required days , cleaning the flooring space manually etc. but excluding GST complete in all respect as directed by the Engineer-in-charge.	6.87	Sqm		
3	Providing and fixing of Suspended ceiling system with Prima Fine Fissured Micro lock tiles of size 600mm x 600mm with humidity resistance of 99%. Silhouette reveal profile grid system with 15mm white flanges incorporation a 3mm or 6mm central recess. Main runner should be spaced at 1200mm c/c securely fixed to the structural soffit by approved hangers at 1200mm maximum center and not more than 150mm from spliced joints. The last hanger at the end of each main runner should not be greater than 600mm from the adjacent wall. 1200 mm long cross tees to be interlocked between main runners at 600mm centers to from 1200 x 600mm modules. 600x600mm modules to be formed by fitting 600mm long	11.15	Sqm		


	cross tees centrally between the 1200mm cross tees. The 1200mm cross tees to have central birds mouth notches to facilitate fitting of 600mm cross tees. Wall angles in white colour to be secured to walls at 450mm maximum centres.				
4	Fixing of Brass Ball Valve (Horizontal plunger type) conforming to IS 1703-1977 as per specification complete.	1.00	Each		
5	Fixing Chromium Plated brass soap dish complete with Chromium Plated brass brackets fixed to wooden plugs with Chromium Plated brass screws or as per specification	1.00	Each		
6	Fixing Porcelain Flat back standing Urinal (Gents) 380x580x350 including connecting the urinal of White vitreous china clay half stall urinal flat back 580x380x350 mm sizes respectively with waste pipe by means of white lead mixed with chopped hemp etc all complete as per specification.	1.00	Each		
7	Supplying all materials, labours, T&P and fitting and fixing of the following size of CPVC pipe with socket and screw joints in walls and floors including supplying of required number of fittings of approved make including cutting threads to pipes and pipes to length, including wastage,etc for fitting to the walls with supply of holder ats, clamps, fixing wooden plugs in walls, including testing of pipe line for water tightness complete as per IS specification including cost, conveyance and taxes of all materials all complete as per PH specification and direction of Engineer-in-charge.	15.00	Mtrs		
8	Supplying all materials, labours, T&P and fitting and fixing of the 110/100mm size of UPVC pipe with socket and screw joints in walls and floors including supplying of required number of fittings of approved make including cutting threads to pipes and pipes to length, including wastage,etc for fitting to the walls with supply of holder ats, clamps, fixing wooden plugs in walls, including testing of pipe line for water tightness complete as per IS specification including cost, conveyance and taxes of all materials all complete as per PH specification and direction of Engineer-in-charge.	32.00	Mtrs		
9	Fixing of CP Brass Angle Stop Cocks conforming to IS:781-1995 of the following nominal sizes as per specification complete.	2.00	Each		
10	Recessed wiring to light point / fan point / exhaust fan point / call bell point with 1.5 sq.mm FR PVC insulated single core multistrand copper conductor of ISI marked with 20 mm dia non-metalic PVC flexible conduit with 5 Amp, 250 V piano type switch ISI marked and ceiling rose ISI marked mounted on MS box having front bakelite cover of suitable size , MS box with 1.5 sq.mm FR PVC insulated single core multistrand copper conductor as earth wire including all accesories and connection as per direction of Engineer in Charge. (Make of wire Finolex / L&T / Anchor / Havel's / V Guard)	6.00	Each		

11	Supply and fixing of 18W LED Panel Light with cutting of hilex celing & fixing with alumuniam chanel hanging interlucking clamps ets complite as per direction of Engineer in charge.	6.00	Each	
				TOTAL
				GST 18%
				Grand TOTAL

Terms and conditions of execution:

1. The dealer / registered contractor shall submit copies of valid authorisation PAN / GST clearance certificate.
2. Tender should be submitted within 7 days of Notice.
3. The work shall be completed within 15days from the date of issues of work order.
4. 100% payment shall be made after completion of work and verification thereof as per Purchase Order/ Work Order.

The sealed tender should reach the undersigned on or before 3:30 P.M. on dated 17.11.2023. The authority reserves the right accept / reject any or all the tender without assigning any reason thereof.


General Manager (Admn)

C.C.

1. PA to CEO, OCAC for kind information of CEO, OCAC.
2. G.M. (Admin), OCAC for kind information
3. General Manager (Finance), OCAC for kind information.
4. Notice Board for information of all bidders.
5. Sri B. K. Mohanty, DPO to publish the notice in OCAC website.